

MDOT Ancillary Structures Preservation Unit

Highway Maintenance Conference – Bay City

April 25th, 2023

Presented by: Michelle Harris (TT 10)



SORRY, FOLKS!

DUE TO A LACK OF TRAINING
AND PREPLANNING, WE'VE MISJUDGED
OUR LADDER PLACEMENT
AND I CAN'T REACH YOU...

HANG ON WHILE WE
REPOSITION!



PAUL COMBS
ARTISTIC SKETCHES
FIRE ENGINEERING

ANCILLARY STRUCTURES PROGRAM



Ancillary Structures Unit

Who are we?

What do we do?

What's new?



Ancillary Structures Crew

Michelle O'Neill – Ancillary Structures Program Manager
(she's in Charge)

- Ph: 269-998-4044

Vacant LTE 13 – Statewide Ancillary Structures Development Specialist

- Ph: Vacant

Sue Taylor- Sign Cantilever/Truss Specialist (TT 11)

- Ph: 517-636-4086

Tom Zurburg- Noise wall Specialist (TT 12)

- Ph: 517-712-0137

Michelle Harris- (That's me) (TT 10)

- Ph: 517-281-8384

Agenda

Inventory and Asset Management

New Features/ Innovations

Retaining Wall Update

Inspections

Maintenance



Inventory and Asset Management

A solid orange horizontal bar is positioned at the bottom of the slide, extending across most of the width.

MDOT's Ancillary Structures

Culvert Less
than 10-Foot
Span

Retaining Wall

Truss Structure

Embedded Pole
(includes Wood
Pole)

Spun Concrete
Pole

Steel Strain
Pole

Noise Wall

Mast Arm

Dynamic
Message Sign
(DMS)

Frangible Pole
Structure

Non-Frangible
Pole Structure

High Mast
Lighting Tower
(HMLT)







Communication
Tower

Environmental
Sensor Station

Program Reporting Web Page

- Objective:
 - Present inspection findings in easily understood format (including photos)
- Audience:
 - DOT staff *NOT* working inside the AS program and unfamiliar with the data structure

MDOT Michigan Department of Transportation | **DRAFT Ancillary Structures Program Viewer v3.0**

	<h3>Cantilever and Truss</h3> <table border="1"> <thead> <tr> <th># Structures</th> <th># Inspections</th> <th># Work Recs</th> <th># RFAs</th> </tr> </thead> <tbody> <tr> <td>1,912</td> <td>1,114</td> <td>526</td> <td>140</td> </tr> </tbody> </table>	# Structures	# Inspections	# Work Recs	# RFAs	1,912	1,114	526	140		<h3>Retaining Wall</h3> <table border="1"> <thead> <tr> <th># Structures</th> <th># Inspections</th> <th># Work Recs</th> <th># RFAs</th> </tr> </thead> <tbody> <tr> <td>464</td> <td>197</td> <td>37</td> <td>13</td> </tr> </tbody> </table>	# Structures	# Inspections	# Work Recs	# RFAs	464	197	37	13
# Structures	# Inspections	# Work Recs	# RFAs																
1,912	1,114	526	140																
# Structures	# Inspections	# Work Recs	# RFAs																
464	197	37	13																
	<h3>Culvert Less Than 10 Foot Span</h3> <table border="1"> <thead> <tr> <th># Structures</th> <th># Inspections</th> <th># Work Recs</th> <th># RFAs</th> </tr> </thead> <tbody> <tr> <td>44,228</td> <td>7,988</td> <td>3,382</td> <td>80</td> </tr> </tbody> </table>	# Structures	# Inspections	# Work Recs	# RFAs	44,228	7,988	3,382	80		<h3>Dynamic Message Sign</h3> <table border="1"> <thead> <tr> <th># Structures</th> <th># Inspections</th> <th># Work Recs</th> <th># RFAs</th> </tr> </thead> <tbody> <tr> <td>COUNT({OBJE STID})</td> <td>COUNT({AssetG STID})</td> <td>COUNT({Global ID})</td> <td>COUNT({Global ID})</td> </tr> </tbody> </table>	# Structures	# Inspections	# Work Recs	# RFAs	COUNT({OBJE STID})	COUNT({AssetG STID})	COUNT({Global ID})	COUNT({Global ID})
# Structures	# Inspections	# Work Recs	# RFAs																
44,228	7,988	3,382	80																
# Structures	# Inspections	# Work Recs	# RFAs																
COUNT({OBJE STID})	COUNT({AssetG STID})	COUNT({Global ID})	COUNT({Global ID})																
	<h3>Noise Wall</h3> <table border="1"> <thead> <tr> <th># Structures</th> <th># Inspections</th> <th># Work Recs</th> <th># RFAs</th> </tr> </thead> <tbody> <tr> <td>COUNT({Global ID})</td> <td>COUNT({AssetG STID})</td> <td>COUNT({Global ID})</td> <td>COUNT({Global ID})</td> </tr> </tbody> </table>	# Structures	# Inspections	# Work Recs	# RFAs	COUNT({Global ID})	COUNT({AssetG STID})	COUNT({Global ID})	COUNT({Global ID})		<h3>Environmental Sensor Station</h3> <table border="1"> <thead> <tr> <th># Structures</th> <th># Inspections</th> <th># Work Recs</th> <th># RFAs</th> </tr> </thead> <tbody> <tr> <td>COUNT({Global ID})</td> <td>COUNT({AssetG STID})</td> <td>COUNT({AssetG STID})</td> <td>COUNT({AssetG STID})</td> </tr> </tbody> </table>	# Structures	# Inspections	# Work Recs	# RFAs	COUNT({Global ID})	COUNT({AssetG STID})	COUNT({AssetG STID})	COUNT({AssetG STID})
# Structures	# Inspections	# Work Recs	# RFAs																
COUNT({Global ID})	COUNT({AssetG STID})	COUNT({Global ID})	COUNT({Global ID})																
# Structures	# Inspections	# Work Recs	# RFAs																
COUNT({Global ID})	COUNT({AssetG STID})	COUNT({AssetG STID})	COUNT({AssetG STID})																

Current Tasks & Initiatives

- Data Collection and Condition Assessment
- Review and Approval of Shop Drawings
- Requests for Information (RFIs)
- Project Scoping and Design Services

Asset Type	Quantity
Culvert Less than 10-Foot Span	44,051
Retaining Wall	456
Cantilever Structure	918
Truss Structure	832
Embedded Pole (includes Wood Pole)	390
Spun Concrete Pole	297
Steel Strain Pole	386
Noise Wall	274
Mast Arm	97
Dynamic Message Sign (DMS)	193
Frangible Pole Structure	760
Non-Frangible Pole Structure	946
High Mast Lighting Tower (HMLT)	157
Communication Tower	23
Environmental Sensor Station	102

Purpose and Need:

- Development of ancillary structure design, construction, maintenance and management for comprehensive asset management

Main Objectives of the Program:


1. Develop and maintain an AS database framework
2. Collect and manage assets inventory and condition ratings
3. Develop and update standard plans and details
4. Scoping studies and preliminary engineering

Ancillary Structures Program

- Program Management Consultant (PMC) model
 - PMC operates as an extension of MDOT
- PMC service areas:
 - Data management, coordination, and reporting
 - Inspections, inventory, data collection
 - Design standard reviews and updates
 - Scoping and preliminary engineering
 - Special inspections or assessments



Program Management Consultant (PMC) Team



Shop Drawing Review & Approval



Centralized and Standardized
Review of Shop Drawings




Structural Engineering Experts
for Calculations Reviews





Fabrication Expert Review of
Shop Drawing Details



New Features and Innovations



Inspection Procedures & MiASIM




<https://www.michigan.gov/mdot/programs/bridges-and-structures/structure-preservation-and-management/ancillary-structures>

Data Collection & Condition Assessment


- Used ArcGIS Fieldmaps
- QA/QC Process
 - QC App (Web AppBuilder)
- Training/Certifications
- Live and Virtual Option



Program Data Refinement Process



New Labeling system for Cantilever Truss's and Lighting Towers



Retaining Wall Update

MDOT Michigan Department of Transportation

DRAFT Ancillary Structures Program Viewer v3.0

Retaining Wall Inspection Viewer

Search

- RW-000048 Metro Retaining Wall
- RW-000021 Metro Retaining Wall
- RW-000022 Metro Retaining Wall

Structure Number	RW-000048
City	City of Detroit
created_date	8/12/2021, 4:10 PM
Foundation Type	
Job Number	
Built	

Inventory - RW-000048

[Inventory Details](#)

Inspection - 9/29/2021 2:06 PM

[Inspection Details](#)

Powered by Esri



Retaining Wall Asset Management

- Developing an Inventory
- Data Dictionary
 - Inventory
 - Inspection
- Components, Elements and Rating System


Developing an Inventory

- Inventory being collected using MDOT staff & Consultants
- Trying to Expand existing inventory
- Roughly **465 Retaining walls** accounted for

Definition

An earth retaining structure that retains and stabilizes an unstable soil mass by means of lateral support or reinforcement, with a height of 4 feet or greater and the angle of face inclination greater than 70 degrees from horizontal.

Retaining walls join end to a soil and the other end to either soil, a bridge abutment, or other structure(s)



The background is a dark-themed map of Michigan with various cities and towns labeled. Several colored markers are placed on the map, representing retaining walls. A legend box is overlaid on the top right of the map.

Layers Legend X

Retaining Wall Inventory Verification

- Concrete Cantilever Retaining Wall
- Mechanically Stabilized Earth (MSE)
- Metal / Sheet Pile Retaining Wall
- Gabion Retaining Wall
- Other
- Geosynthetic Reinforced Soil (GRS)
- Modular/Segmental Block Wall
- Post and Panel Wall

Retaining Wall Naming dictionary

- General view of the wall (usually requires many similar photos)
- General view of top of wall
- Typical joint photos

Table 3.5.2: Retaining Wall and Noise Wall Photograph Naming Convention

<i>Photo Name</i>	<i>Description</i>
Wall_Entire_Front	General View of entire wall (retaining and noise walls)
Wall_Entire_Back	General View of entire wall (noise walls only)
Wall_Top	General view of top of wall
Wall_Joint	Typical joint photo
Wall_Attachment	Typical attachment

Note: Photo sequence should coincide with inspection direction for the walls.

Inspections

- Rating Systems
- RFA vs Work Rec



Component Rating System

Table 7.1.2: Component Rating System

Component Rating	Condition	Condition State
9	NEW	Like new, within normal range for a newly installed structure.
8	GOOD	Only minor distress or deterioration
7	GOOD	Some problems noted
6	SATISFACTORY	Some moderate or multiple indications of distress/deterioration
5	FAIR	Moderate or multiple indications of distress/deterioration affecting performance
4	POOR	Significant distress
3	SEVERE	Significant distress/deterioration with potential for local failure
2	CRITICAL	Advanced deterioration with potential for failure of primary structural elements
1	IMMINENT	Imminent failure which could threaten public safety
0	FAILED	Failure has occurred


Element Rating System

Rate each element that is present for the structure using the 4-level scale from Good to Severe based on the observed conditions identified during the on-site inspection.

	1	2	3	4	
	Good	Fair	Poor	Severe	Not Rated
Action Indicated	No action is recommended. Note in inspection report only.	No immediate action is recommended but more frequent inspection may be warranted. Maintenance personnel should be informed.	Inspector evaluates need for corrective action and makes recommendations in inspection report.	Corrective action is required and urgent. Engineering evaluation is required to specify appropriate repair.	No action is required. (Except when review could not be performed due to conditions.)
Condition Description	Like new with little or no deterioration. Structurally sound and functionally adequate.	Minor to moderate deterioration. Structurally sound with adequate function.	Significant deterioration. May not have adequate function. Maintenance or repair required.	Major deterioration. Failure may have occurred. Requires maintenance, repair, or replacement.	The element was not part of the system design and is not required for functional adequacy. This includes items missing due to vandalism. Also includes inaccessible items that need to be reviewed.

BUREAU of BRIDGES

Example Retaining Wall Component vs Element



Work Recommendations

- Work recommendations are used for maintenance related issues, **not safety related**
 - Immediate action is not required; however, a work recommendation is part of the inspection process and is completed by the inspector as part of their routine inspection.
 - Inspectors are responsible for clearly documenting the asset conditions
 - Inspectors are responsible for photographing their findings for others to understand field conditions to take appropriate action

Request for Action (RFA)

- **Conditions where public safety may be a concern.**
 - **Priority Level 1** – repairs, mitigation or monitoring is required **as soon as reasonably possible** for public safety. Onsite presence may be required until deficiency is addressed
 - Site personnel to immediately have a brief consultation with qualified personnel with structural engineering expertise
 - Emergency action guidance is provided in the following MDOT memo:
https://www.michigan.gov/documents/mdot/MDOT_Memo_on_Bridge_Closure_policy_final_703291_7.pdf
 - **Priority Level 2** – repairs, mitigation or monitoring is to be completed **within 1 year** or as determined by a qualified engineer
 - **Priority Level 3** – repaired, mitigated or monitored as determined **per engineering judgement**. The deficiency is not deemed to be critical threat to public safety but could be if left unaddressed.

Maintenance Efforts




Inspection Findings - culverts



Figure 8.2.17: Blocked inlet



Inspection findings – Retaining & Noise Walls





Inspection Findings – Sign Foundations

Requests for Action (RFAs) for Sign Support Structures

AVERAGE CLOSURE DURATION (by number of days)



Following the implementation of MDOT's new asset management program, average closure duration has been **reduced from 9 months to 1 month.**

Average closure duration
Q3 2021

293 days

First Request for Action
(RFA) closed

March 2, 2022

Average closure duration
after first RFA closed

39 days

Sign Support RFA Close Out

Contact Information

Michelle O'Neill – Ancillary Structures Program Manager
(she's in Charge)

- Ph: 269-998-4044

Vacant LTE 13 – Statewide Ancillary Structures Development Specialist

- Ph: Vacant

Sue Taylor- Sign Cantilever/Truss Specialist (TT 11)

- Ph: 517-636-4086

Tom Zurburg- Noise wall Specialist (TT 12)

- Ph: 517-712-0137

Michelle Harris- (That's me) (TT 10)

- Ph: 517-281-8384

Recap

Inventory and Asset Management

New Features/ Innovations

Retaining Wall Update

Inspections

Maintenance



Thank you!!